



Extension of entrance area Polyclinic VUmc

The project involved the demolition and complete redesign of the entrance area. The new entrance area includes a restaurant including kitchen, new reception counters, offices, meeting rooms, washrooms, revolving door and waiting rooms.

The project

The scope of works included a new Bolidt floor, metal ceilings, metal stud walls with designer wall coverings, diverse new interior elements (counters, sofas, information benches, etc.), tiling, wooden restaurant floor and installing a new revolving door. The project was located in the middle of the busiest part of the hospital; thousands of visitors and staff pass through the main entrance everyday. The measures taken to avoid nuisance during the works included: shifted work hours, closing off the construction area with a fabric wall, creating negative pressure in the construction area by applying a ventilation inlet and outlet outside of visiting hours.

Main Contractor

The project was delivered by [MedicomZes](#) (a trading name of Visser & Smit Bouw bv).



Facts and figures

Site

Amsterdam

Client

VU medisch centrum Amsterdam

Status

Completed

Contract type

Specification & Drawings

Learn more?

 info@visserensmitbouw.nl

 <https://www.visserensmitbouw.nl>

 +31 10 313 10 00